

HYDERABAD METRO RAIL LIMITED
(HMR, a State-owned Public Enterprise of Govt. of Telangana)



NOTICE INVITING QUOTATION

NIQ: EE-IV:/HMR/Interiors/2016-17 dt:09.01.2017

Sub HMR- Providing interiors to MDs Chamber on 4th floor
: HMR Corporate office, Begumpet quotations called -
Reg.

<< <> >>

Quotations are invited from the reputed agencies with expertise in Providing interiors for MDs Chamber on 4th floor HMR Corporate office, Begumpet in sealed covers with the following specifications:

Sl.No	Description of work	Unit
1	Full height storage unit: Supply and fixing of full height storage unit with 25mm thick top, and box made with 18mm thick MDF with veneer with aluminium profile shutters fixing with soft closer Hinges with inside glass shelves of size W-3'+1'6"xD-1'6"xH-7' including cost of all materials, accessories, labour, fixing at site charges, etc complete for finished item of work as per the directions of the Engineer-in-charge.(31.5Sft)	Job
2	Low Level storage unit: Supply and fixing low level storage unit with 25mm thick top and box made with 18mm thick MDF with veneer using with soft close hinges wit in built Handles of Gola profile of W-10'xD-1'6"xH-2'6" including cost of all materials, accessories, labour, fixing at site charges, etc complete for finished item of work as per the directions of the Engineer-in-charge.(25.00Sft)	Job
3	Low level Storage unit: Supply and fixing low level storage unit with of 25mm thick top and box made with 18mm thick MDF with veneer. Drawers with pull and push channel of size W-12'xD-1'xH-1' (12Sft) including cost of all materials, accessories, labour, fixing at site charges, etc complete for finished item of work as per the directions of the Engineer-in-charge	Job
4	Book Shelf: Supply and fixing of 25mm thick box made	Job

	with MDF+veneer size:W-4'+4'xD-1'xH-5'6" (44sft) including cost of all materials, accessories, labour, fixing at site charges, etc complete for finished item of work as per the directions of the Engineer-in-charge	
5	Providing Back panelling sheet behind Buddha (as per design)-Material: MDF 3d panelled sheet size:4'x5'6" (22sft) including cost of all materials, accessories, labour, fixing at site charges, etc complete for finished item of work as per the directions of the Engineer-in-charge.	Job
6	Supply and fixing of 8mm thick glass shelves in the aluminium doors including cost of all materials, accessories, labour, fixing at site charges, etc complete for finished item of work as per the directions of the Engineer-in-charge	Job
7	Providing doors beautification with laminate for 2 Nos doors, including cost of all materials, accessories, labour charges, etc complete for finished item of work as per the directions of the Engineer-in-charge	Job
8	Supply and fixing of 25mm thick top and box made with 18mm thick MDF with veneer mat finish polish of size:W-8'xD-1'2"xH-1' (8sft) including cost of all materials, accessories, labour charges, etc complete for finished item of work as per the directions of the Engineer-in-charge	Job
9	Providing wall panelling,frame made with plywood with 50mmx36mm thick with regular 600mmx600mm Grid with horizontal and verticals.Finishing of 12mm thick MDF with veneer panelling up to ceiling level with required accessories including cost of all materials,accessories,labour charges,etc complete for finished item of work.(650 sft) as per the directions of the Engineer-in-charge	Job

Schedule for receipt of quotations.

	Date	Time
Last Date for receipt of quotations	12.01.2017	3:00PM
Opening of quotation	12.01.2017	3:30PM

Sd/-
Executive Engineer-IV

